BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
42	Providing and fixing of Elliptical Cross Trainer (GP-666) – Easier, More effective Cardio. Stay fit Elliptical Cross Trainer GP- 666 provides a natural, low-impact stride, so users can work out longer and harder. And our design lets them target various muscle groups just by changing the resistance levels. Completely smooth and natural feel Reduces joint stress and minimizes fatigue. Moving handlebars for a total-body workout of Dimension: 80" (L) x 28" (W) x 70" (H); Strides: 20 Inches natural strides. Maximum Watt: 250 Watts; Resistance Level: 16 Levels. Resistance System: Electro-Magnetic resistance; Power: Self generated power system; Programs: 06 Programs – manual, HRC, random, weight loss, CV and hill intervals. Drive System: Centre design drive, super silent poly-V belt driven. Pedals: Self balancing, close spacing, enlarge, impact-absorbing, fit to any size user and provides gentle movements to reduce lower body stress. Centre of Gravity: Low COG combined with a balanced frame which prevents rocking. Cardio Monitor: In built metallic pulse sensor provided with U bar style and upper handle grips enables to the cardio monitoring on board. Display: Dot matrix LED, computerized console. Display Feedback: Multi feedback read out instantly displays time, distance, RPM, calories, heart rate, speed, work (Resistance) levels, watts and mets. User Weight: 180 Kgs. Transportation: Transportation wheels for easy movements. Accessory Holder: Water bottle and mobile phone holder. Rating: Commercial. Step-up Height: 08 Inches easy step-up height. Strides Wheel: Dual wheel track, fiber glass reinforced nylon wheel with high quality bearing. Frame Structure: Arched support frame for maximum durability and stability. Frame Finishing: Proprietary two coat powder process. Rust Proof: All frame structures electro statically powder coated to ensure minimum corrosion and chip resistance as per Engineer in Charge of the work.	No	1.00	238425.00	Rupees Two Lakh Thirty Eight Thousand Four Hundred Twenty Five Only
43	Providing and fixing of Dumbbells Rack for easy racking and unracking; ideal for larger dumbbell sets; easy to pick and place it back ; hard chrome dumbbells coated with rubber coating for better life and safety with 137cm x 47cm x 87cm as per Engineer in Charge of the work.	No	1.00	57222.00	Rupees Fifty Seven Thousand Two Hundred Twenty Two Only
44	Providing and fixing of SF – Biceps/ Triceps with Bar catch design for each re-racking Adjustable oversized arm pad 102 cm (L) x 71 cm (W) x 82 cm (H) as per Engineer in Charge of the work.	No	1.00	181203.00	Rupees One Lakh Eighty One Thousand Two Hundred Three Only
45	Supplying of Casting Plate with rubber plating as per Engineer in Charge of the work.	No.	1.00	170000.00	Rupees One Lakh Seventy Thousand Only
46	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum.	86.34	209.00	Rupees Two Hundred Nine Only
47	Providing and laying in position plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted,in foundation,plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum.	30.00	6199.00	Rupees Six Thousand One Hundred Ninety Nine Only
48	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating,curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20	Cum.	11.34	7200.00	Rupees Seven Thousand Two Hundred Only
49	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	Sqm	200.00	1290.00	Rupees One Thousand Two Hundred Ninety Only
50	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork,curing,including cost of all materials, labour, hire charges of machinery, loading,unloading, lead and lift, transportation etc., complete	No.	178.00	335.00	Rupees Three Hundred Thirty Five Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
51	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	28.00	71.00	Rupees Seventy One Only
52	SUPPLYING AND FIXING OF LEG PRESS DOUBLE OF SAFE AREA : 2.8MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS PIPE, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK.	No.	2.00	119000.00	Rupees One Lakh Nineteen Thousand Only
53	SUPPLYING AND FIXING OF FUN WALKER DOUBLE OF SAFE AEA : 3 MTR X 2 MTR, MAIN FRAME : 100 NB GI B-class Pipe, LEG FRAME : 32 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMENANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BPLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	170000.00	Rupees One Lakh Seventy Thousand Only
54	SUPPLYING AND FIXING OF PENDULUM DOUBLE OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B- class Pipe, LEG FRAME : 40 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOULTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	109000.00	Rupees One Lakh Nine Thousand Only
55	SUPPLYING AND FIXING OF SHOULDER PRESS DOUBLE OF SAFE AREA : 4 MTR X 2.5 MTR OF CENTRE PIPE : 100 NB GI B-class Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, NUT BOLT CAP : Nylon 66 injection moulded, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK	No.	2.00	195000.00	Rupees One Lakh Ninety Five Thousand Only
56	SUPPLYING AND FIXING OF CYCLE TWO WAY OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B-class Pipe, ARM FRAME : 40 NB GI B-class Pipe, HANDLE FRAME : 20 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No	2.00	119000.00	Rupees One Lakh Nineteen Thousand Only
57	SUPPLYING AND FIXING OF TAI CHI SPINEER DOUBLE OF SAFE AREA : 2 MTR. DIA, MAIN FRAME : 100NB GI B-class Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SPINNING RING : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STELL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No	3.00	99000.00	Rupees Ninety Nine Thousand Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
58	SUPPLYING AND FIXING OF TWISTER THREE WAY OF SAFE AREA : 2.5 MTR. DIA, MAIN FRAME : 100 NB GI B – class Pipe, ARM FRAME : 32 NB GI B – CLASS Pipe, HANDLE FRAME : 20 NB GI B – CLASS Pipe, TWISTER DISC : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection mouded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	99000.00	Rupees Ninety Nine Thousand Only
59	SUPPLYING AND FIXING OF CHEST PRESS DOUBLE – OF SAFE AREA : 4 MTR X 2.5 MTR, OF CENTRE PIPE : 100 NB GI B-class Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HNDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	209000.00	Rupees Two Lakh Nine Thousand Only
60	SUPPLYING AND FIXING OF FUN ROVER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B-class Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARINGS : PERMANRNT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	66759.00	Rupees Sixty Six Thousand Seven Hundred Fifty Nine Only
61	SUPPLYING AND FIXING OF FUN RIDER, SAFE AREA: 2.5 MTR X 1.5 MTR., MAIN FRAME: 80 NB GI B-class Pipe, SEAT FRAME: 80 NB GI B-CLASS Pipe, HANDLE FRAME: 32 NB GI B-CLASS Pipe, SEAT: LLDP Plastic, PIPE CAP: Nylon 66 injection moulded, BEARING CAP: Nylon 66 injection moulded, BEARING HOUSHING AND PIN: Seamless Pipe & Round Bar, NUT BOLTS CAP: Nylon 66 injection moulded, BEARINGS: PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS: HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT: DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	166897.00	Rupees One Lakh Sixty Six Thousand Eight Hundred Ninety Seven Only
62	SUPPLYING AND FIXING OF STEP TRAINER OF SAFE AREA : 3 MTR X 1.5 MTR, MAIN FRAME : 100 NB GI B-class Pipe, BOTTOM FRAME : 40 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARNING CAP : Nylon 66 injection moulded BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	200277.00	Rupees Two Lakh Two Hundred Seventy Seven Only
63	SUPPLYING AND FIXING OF ROLLING BARREL DOUBLE OF SAFE AREA : 2.8 MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOULTS : HIGH TENSILE STEEL, GALBANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK.	No.	3.00	157360.00	Rupees One Lakh Fifty Seven Thousand Three Hundred Sixty Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
64	Providing and erecting direction and place identification retro- reflectorised sign as per IRC :67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801Using Type IV sheeting	Sqm	1.00	8106.00	Rupees Eight Thousand One Hundred Six Only
65	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum.	191.48	190.00	Rupees One Hundred Ninety Only
66	Providing and laying in position plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted,in foundation,plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum.	40.00	5722.00	Rupees Five Thousand Seven Hundred Twenty Two Only
67	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20	Cum.	71.48	6675.00	Rupees Six Thousand Six Hundred Seventy Five Only
68	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , ncluding attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.	Sqm	24.00	333.00	Rupees Three Hundred Thirty Three Only
69	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	400.00	104.00	Rupees One Hundred Four Only
70	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.	Rmt	240.00	133.00	Rupees One Hundred Thirty Three Only
71	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork,curing,including cost of all materials, labour, hire charges of machinery, loading,unloading, lead and lift, transportation etc., complete.	No	1424.00	352.00	Rupees Three Hundred Fifty Two Only
72	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	72.00	66.00	Rupees Sixty Six Only
73	Providing and constructing standard rubber flooring for Outdoor areas using rubber membrain of 12mm thick to be layed over Praepared Cement Morter/Concrete surface using CM1:6 Beneath ruber membrain including cost of all materials labour packing joints and mortor, finishing curing all Lead & lift transportation and also including all applicable taxes etc, cmplete as per direction of engineer incharges of work.	Sqm	400.00	5722.00	Rupees Five Thousand Seven Hundred Twenty Two Only
74	SUPPLYING AND FIXING OF LEG PRESS DOUBLE OF SAFE AREA : 2.8MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS PIPE, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK	No.	4.00	114444.00	Rupees One Lakh Fourteen Thousand Four Hundred Forty Four Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
75	SUPPLYING AND FIXING OF FUN WALKER DOUBLE OF SAFE AEA : 3 MTR X 2 MTR, MAIN FRAME : 100 NB GI B-class Pipe, LEG FRAME : 32 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMENANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BPLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	6.00	166897.00	Rupees One Lakh Sixty Six Thousand Eight Hundred Ninety Seven Only
76	SUPPLYING AND FIXING OF PENDULUM DOUBLE OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B- class Pipe, LEG FRAME : 40 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOULTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	100138.00	Rupees One Lakh One Hundred Thirty Eight Only
77	SUPPLYING AND FIXING OF SHOULDER PRESS DOUBLE OF SAFE AREA : 4 MTR X 2.5 MTR OF CENTRE PIPE : 100 NB GI B-class Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, NUT BOLT CAP : Nylon 66 injection moulded, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK	No.	4.00	190740.00	Rupees One Lakh Ninety Thousand Seven Hundred Forty Only
78	SUPPLYING AND FIXING OF CYCLE TWO WAY OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B-class Pipe, ARM FRAME : 40 NB GI B-class Pipe, HANDLE FRAME : 20 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	114444.00	Rupees One Lakh Fourteen Thousand Four Hundred Forty Four Only
79	SUPPLYING AND FIXING OF TAI CHI SPINEER DOUBLE OF SAFE AREA : 2 MTR. DIA, MAIN FRAME : 100NB GI B-class Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SPINNING RING : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STELL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	5.00	100138.00	Rupees One Lakh One Hundred Thirty Eight Only
80	SUPPLYING AND FIXING OF TWISTER THREE WAY OF SAFE AREA : 2.5 MTR. DIA, MAIN FRAME : 100 NB GI B – class Pipe, ARM FRAME : 32 NB GI B – CLASS Pipe, HANDLE FRAME : 20 NB GI B – CLASS Pipe, TWISTER DISC : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection mouded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	100138.00	Rupees One Lakh One Hundred Thirty Eight Only

For K. DAMODAR & CO.